BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Improvements of roads and drains at Kattigenahalli to Kogilu Main and Cross Roads in Ward No.05 (Jakkur)

SNo	Quantity	Item Name	Unit	Approved Rates of Sri.SATHYA B R (R M ENTERPRISES.....)	
				In figures	In words
1	2799.96	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1,KPWD SR 2018-19) 10km lead= 57+2.0x1.28x10 =82.60	Cum	226.13	Rupees Two Hundred Twenty Six And Paise Thirteen Only
2	384.24	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18,KPWD SR 2018-19)	Cum	5683.25	Rupees Five Thousand Six Hundred Eighty Three And Paise Twenty Five Only
3	44.44	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specificatio (I No-28.8.2,P No-229,KPWD SR 2018-19)	Tonne	75796.05	Rupees Seventy Five Thousand Seven Hundred Ninety Six And Paise Five Only
4	737.36	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm (I No-37.59.2,P No-271,KPWD SR 2018-19)	Cum	7414.62	Rupees Seven Thousand Four Hundred Fourteen And Paise Sixty Two Only
5	1335.15	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	2474.78	Rupees Two Thousand Four Hundred Seventy Four And Paise Seventy Eight Only
6	14.40	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. KPWD SR 2018-19	Sqm	5725.95	Rupees Five Thousand Seven Hundred Twenty Five And Paise Ninety Five Only

For R. M. ENTERPRISES

Contractor/Partner

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri.SATHYA B R (R M ENTERPRISES.....)	
				In figures	In words
7	891.44	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 10km lead= (I No-19.14,P No-143,KPWD SR 2018-19)	Cum	43.67	Rupees Forty Three And Paise Sixty Seven Only
8	9616.20	KSRRB 300-46. Scarifying by mechanical means stone metal crust 50mm to 100mm thick by along with 20mm premix carpet / surface dressing and stacking of old serviceable materials including cost of all labour charges, HOM complete as per specifications.(P.No-146,I No-19.52)	Sqm	42.70	Rupees Forty Two And Paise Seventy Only
9	1224.80	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147,KPWD SR 2018-19)	Sqm	6.79	Rupees Six And Paise Seventy Nine Only
10	1141.56	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications.(I No-20.5,P No-153,KPWD SR 2018-19)	Cum	2091.43	Rupees Two Thousand Ninety One And Paise Forty Three Only
11	3028.72	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18,KPWD SR 2018-19)	Cum	2098.22	Rupees Two Thousand Ninety Eight And Paise Twenty Two Only
12	13461.00	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6,KPWD SR 2018-19) Issue rate Dated -02-07-2020	Sqm	31.06	Rupees Thirty One And Paise Six Only
13	17179.40	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7,KPWD SR 2018-19) Issue rate Dated -02-07-2020	Sqm	13.59	Rupees Thirteen And Paise Fifty Nine Only

For R. M. ENTERPRISES

Partner

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri.SATHYA B R (R M ENTERPRISES.....)	
				In figures	In words
14	673.05	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 505 of MORTH V revisionusing 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen (P.No-160,I No-21.17.6,KPWD SR 2018-19) Issue rate Dated -02-07-2020	Cum	6726.24	Rupees Six Thousand Seven Hundred Twenty Six And Paise Twenty Four Only
15	687.18	Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. – do – using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4 % of modified bituminus binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic) (P.No-171,I No-21.78.12,KPWD SR 2018-19) Issue rate Dated -02-07-2020	Cum	7921.80	Rupees Seven Thousand Nine Hundred Twenty One And Paise Eighty Only
16	670.20	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15,KPWD SR 2018-19)	Sqm	476.28	Rupees Four Hundred Seventy Six And Paise Twenty Eight Only
17		GST @ 12%			

For R. M. ENTERPRISES

Partner
Contractor

Executive Engineer
Project Division
Yelahanka Zone